BRUHAT BENGALURU MAHANAGARA PALIKE
EXECUTIVE ENGINEER (ELECRICALS) DASARAHALLI ZONE
Schedule -B
Indent Number:BBMP/2021-22/EL/WORK_INDENT49663

Name Of Work: Providing LED Street lights/Poles/Control switches/control wires at Dark/volernabal places In Ward no 13,14 & 15

SNo	Item Name	Unit	Estimate Quantity	Rates Quoted by Contractor NAGARAJU LINGAIAH (VEDHA ELECTRICALS)	
				In Figures (Rs.)	In Words (Rs.)
1	Supply of LED Streetlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, maximum light intensity should be between 60 degrees to 70 degrees. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mouting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 . Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 2 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED manufacturer & Cree/Nichia/ Lumileds/Osram make LED Source.LED Streetlight 90 Watts	Nos	1727	7661.2	Rupees Seven Thousand Six Hundred Sixty One and Two Paisa Only
2	Supplying and Fixing of mm dia class A GI pipe bracket up to 2 Mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires.Using 32mm dia G I Pipe	each	1727	893.45	Rupees Eight Hundred Ninty Three and Forty Five Paisa Only.
3	Fixing halogen/metal halide / SVL / IL / LED floodlight fitting over existing pole / wall ceiling including clamps, bolts, nuts and wiring using suitable capacity wires.	each	1727	187.25	Rupees One Hundred Eighty Seven and Twenty Five Paisa Only.
4	Wiring for lighting/power circuit using one of PVC insulated 1100V grade, stranded Aluminium wire single core in open or concealed system of wiring.4 sqmm	Mtrs	5000	9.63	Rupees Nine and Sixty Three Paisa Only.

For Vedha Electricals

Proprietor

Executive Engineer (Ele)
Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone

Scanned by CamScanner

Where as the Administratively sanction an esti-
and Sixty Nine Thousand Only) Tech-
BBMP/EIC/TS/13/2021-22, D-
lights/Poles/Control s-
based on the

5	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts, necessary phase separators, handle and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) 100Amps 25kA.	each	50	4847.1	Rupees Four Thousand Eight Hundred Forty Seven and One Paisa Only.
6	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop- Out terminals for 10 Sqmm / 25 Sqmm 3.5 C Al/Ar / Cu/ Ar Cable and branch out 2.5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets 260mmx210mmx116mm	each	50	2197.78	Rupees Two Thousand One Hundred ninty seven and Seventy Paisa only.
7	Supplying of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7098 Part-1, Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975 4 core 16 sqmm	Mtrs	295	160.5	Rupees One Hundred Sixty and Five Paisa Only.
8	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required On wall /Structure 6 sqmm to 16 sqmm	Mtrs	295	32.1	Rupees thirty Two and One Paisa only.
9	1.1 kV, LT Aerial Bunched Cable, comprising to IS-14255: 1995 XLPE insulation Parameter shall be as below 1. Hot Set Test: a) Elongation under Load: 50% (Max) b) Permanent Elongation After Cooloing: 3% (Max) 2. Thermal Aging in oven: a) Tensile Strength: 16 N/mm^2 (Min) b) Elongation 375% (Min) 3 Water Absorption Test a) Water absorbed: 0.5 mg/cm^2 (Max) 4. Carbon Black Content shall be ranging from 2% to 3% 3x25 + 1x25 + 1x16 Sqmm Street light (Insulated Messenger cum Neutral)	Km	1.575	157290	Rupees One Lakh Fifty Seven Thousand Two Hundred Ninty Only.
10	Stringing of 1.1 kV grade Aerial Bunched 3 Core cable of XLPE insulation of size (3x95) (Phase Conductor) + (1x70) (Insulated Messenger Neutral) + (1x25) (Street Light Control)	Km	1.575	24041.83	Rupees Twenty Four Thousand Forty One and Eighty Three paisa Only.

For Vedha Electricals

Proprietor

Executive Engineer (Ele)
Dasarahalli Zone.
Bruhat Bengaluru Mahanagara Palike

Executive Engineer (Ele)
Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone

Scanned by CamScanner